

TOWN OF FARMINGTON
2021 ROAD REPAIR
REQUEST FOR PROPOSALS (RFP)

The Town of Farmington is requesting proposals for cost associated with asphalt overlay projects and also “spot” asphalt patches thorough the township. Each potential bidder should specify if they are submitting a proposal for both the overlay projects and/or “spot” asphalt repairs listed below. Proposals do not have to include both overlay and “spot” repair request. Work may be awarded as a combined project or separating “spot” repairs from overlay repairs.

“Spot” repairs include:

Saw cut existing asphalt at the pre-marked dimensions (pink painted) locations

Remove and dispose of old asphalt material.

Install 3” of new hot mix asphalt material (installed in two 1.5” lifts, compacted in between lifts)

*** indicated spot patches that will require undercutting the existing subsoil material to a minimum depth of 8” (depth based on material discovered), filled in and compact a new crushed aggregate base (1.5-2” limestone breaker run material)

<u>Locations (see Map & Pictures)</u>		<u>Cost</u>
Boltonville Rd. # 1	62’ x 10’	_____
Boltonville Rd. # 2	27’ x 10’	_____
Boltonville Rd. # 3	22’ x 36’	_____
Boltonville Rd. # 4	40’ x 10’	_____
Boltonville Rd # 5	1,560 sq. ft.	_____
Windy Acres #1	6’ x 70’	_____ ***
Scenic Dr. # 1	65’x 8’	_____
Scenic Dr. #2	90’ x 8’	_____
Scenic Dr. # 01	22’ x 5’	_____
Scenic Dr. # 1-0	9’ x 50’	_____
Scenic Dr. # 2-0	6’ x 144’	_____
Scenic Dr. # 3-0	8’ x 47’	_____
Scenic Dr. # 4-0	7’ x 44’	_____
Scenic Dr. # 5-0	7’ x 63’	_____

East Moraine Dr. # 1	6' x 38'	_____	
East Moraine Dr. # 2	7' x 57'	_____	
East Moraine Dr. # 3	8' x 46'	_____	
East Moraine Dr. # 4	7' x 48'	_____	
Maple Tree Rd. # 5	3' x 40'	_____	
Maple Tree Rd. # 6	4' x 35'	_____	
Maple Tree Rd. # 7	6' x 100'	_____	
Maple Tree Rd. # 8	5' x 80'	_____	
Valley View Dr. # 1	20' x 24'	_____	***
Valley View Dr. # 2	90' x 8'	_____	***
Forest View Dr. # 1	45' x 10'	_____	***
Forest View Dr. # 2	20' x 22'	_____	new culvert location (base has been installed)
Forest View Dr. # 3	50' x 9'	_____	
8379 Whitewood Dr.	115' x 6'	_____	***
1347 Shalom Dr.	122' x 25'	_____	(new base material was already installed)
Total		_____	Includes all equipment, labor, supplies

Asphalt overlay areas include:

Wedge mill all existing driveway entrances that require to match private drive material with new road surface.

Wedge across the entire road pavement at each start and stop locations (locations are pre-marked with pink paint)

Remove loose asphalt material and overlay with minimum of 1.5" layer of hot mix surface asphalt material.

- Provide cost option to have new 2' wide gravel shoulder installed and compacted after new pavement is placed, utilizing ¾" crushed limestone material.

Wedge and Overlay locations (See Red on Map)		Overlay Cost	Shouldering Option
Mary Lane	625' x 20' with 75' diameter cul de sac.	_____	_____
Pathfinder Dr.	1,000' x 25'	_____	_____
Fillmore Rd.	850' x 20'	_____	_____
Total for all 3 locations		_____	_____

All work should include labor, equipment and material cost to complete. Work should be completed on or before October 31, 2021, unless agreed upon and specified in the proposal submitted.

The Town of Farmington reserves the right to add additional linear footage length to the proposed overlay locations prior to start of work. The town also reserves the right to choose how much of the itemized list is award based on proposal amounts and budgetary amounts.

A map with specific locations will accompany this request for proposals. Feel free to contact Doug Neumann, Town Chairman, (262.689.1926) with any questions regarding details of the RFP.

Deadline for submittal is July 13, 2021 @ 7:00pm. Proposals will be opened during the Town Meeting scheduled on July 13, 2021 @ 7:00pm

Sealed proposals should be mailed to or dropped at the Town of Farmington Town Hall:

2021 Road Bids

Town of Farmington

9422 STH 144

Kewaskum WI. 53040

